

SECTION 01 43 38

FIELD SAMPLES AND MOCK-UPS

PART 1 – GENERAL

1.01 SECTION INCLUDES

- A. Field samples and mock-ups.

1.02 MEASUREMENT AND PAYMENT

- A. Separate measurement or payment will not be made for work required under this Section. All costs in connection with the work specified herein will be considered to be included with the related item of work in the Bid Schedule of the Bid Form, or incidental to the Work.

1.03 FIELD SAMPLES AND MOCK-UPS

- A. Field samples and mock-ups shall be prepared at the jobsite by the Contractor as specified in the various Sections of these Specifications. Affected finish work shall not be started until the Engineer has approved the field samples and jobsite mock-ups in writing.
- B. Construct and prepare field samples and jobsite mock-ups at designated locations at the jobsite or on the structure as directed by the Engineer.
 - 1. The Contractor shall have product manufacturers inspect and approve field samples and mock-ups, that involve their materials, for proper application or installation of the materials in accordance with their respective instructions and recommendations for the conditions or circumstances involved in the application or installation.
 - 2. The Contractor shall make arrangements with the respective product manufacturers to provide job or field service as specified in Section 01 43 00 - Quality Assurance.
- C. Construct or prepare as many additional samples and mock-ups as may be required, as determined by the Engineer, until desired features, textures, finishes, and colors are obtained. Approved samples and mock-ups shall serve as the standards of quality for the various affected units of work.
- D. Preserve approved field samples and mock-ups for comparison purposes until the affected work is completed and accepted by the District. Finished work shall match the approved field samples and mock-ups.

1.04 NONCONFORMANCE

- A. Completed work that does not exactly match approved field samples and mock-ups will be rejected, and shall be replaced with work that does exactly match the approved field samples and mock-ups at the Contractor's expense.
- B. If the Contractor elects to start work before the Engineer has approved the related field samples or mock-ups, the Contractor does so at the risk of having the work rejected by the Engineer without compensation.

1.05 REMOVAL AFTER COMPLETION

- A. Field samples and mock-ups shall be removed from the jobsite and structures after completion and acceptance of the affected work or otherwise as directed by the Engineer.

PART 2 – PRODUCTS

Not Used

PART 3 – EXECUTION

Not Used

END OF SECTION 01 43 38